

CORRIGENDUM No.2

REQUEST FOR PROPOSAL: UNHCR RFP-260

Construction and renovation work of schools in Raniya District, Sulaymaniyah, Iraq

Lot-1: Construction works of four classrooms and renovation of the existing W.C. building Saryan School in Raniya-Sulaymaniyah Governorate.

Lot-2: Construction of four classrooms and renovation of the existing W.C. Building Hajiyawa School in Raniya-Sulaymaniyah Governorate.

Lot-3: Construction of three classrooms, W.C., and renovation of Gyarang School in Raniya-Sulaymaniyah Governorate.

The original Request for Proposal No. RFP-260 related to Construction and Renovation work of Schools in Raniya District in three (3 LOTS)

Lot-1: Construction works of four classrooms and renovation of the existing W.C. building Saryan School in Raniya-Sulaymaniyah Governorate.

Lot-2: Construction of four classrooms and renovation of the existing W.C. Building Hajiyawa School in Raniya-Sulaymaniyah Governorate.

Lot-3: Construction of three classrooms, W.C., and renovation of Gyarang School in Raniya-Sulaymaniyah Governorate. dated 4th September 2024 is hereby amended as follows:

Annex B LOT2 -BOQ: The row number B6 which is Beams: Provide all materials and cast reinforced concrete (ready mix C 25) for beams and lintels according to the drawings, specifications, and instructions of the site engineer.

The actual quantity is 9.5 m3.

Annex C LOT2- Financial Offer Form: The row number B6 which is Beams: Provide all materials and cast reinforced concrete (ready mix C 25) for beams and lintels according to the drawings, specifications, and instructions of the site engineer.

The actual quantity is 9.5 m3.

Annex B LOT2-BOQ: Metal Door (Qasa): Provide and install decorative metal doors (Qasa) (exported or on-site manufactured) for the main entrance, double-faced of plate thickness 1.50mm including glass pans, door frame 13.5*4.5cm 2.5mm thickness, Film Coated Residential Steel Entrance Door Glassy Finished Style, including special switch, gate lock, door stopper, rubber, polycarbonate filled, special guard bar, thermal paint & metal frames 6*22cm, Mercury glass 15x40cm with 3 cm Styrofoam

polystyrene inside the door, Central lock system, with additional horizontal a lock with three concealed hinges with all necessary works, samples required for final approval.

The actual quantity is 5.5 m2.

Annex C LOT2 - Financial Offer Form: Metal Door (Qasa): Provide and install decorative metal doors (Qasa) (exported or on-site manufactured) for the main entrance, double-faced of plate thickness 1.50mm including glass pans, door frame 13.5*4.5cm 2.5mm thickness, Film Coated Residential Steel Entrance Door Glassy Finished Style, including special switch, gate lock, door stopper, rubber, polycarbonate filled, special guard bar, thermal paint & metal frames 6*22cm, Mercury glass 15x40cm with 3 cm Styrofoam polystyrene inside the door, Central lock system, with additional horizontal a lock with three concealed hinges with all necessary works, samples required for final approval.

The actual quantity is 5.5 m2.

Annex B LOT1-BOQ: Metal Door (Qasa): Provide and install decorative metal doors (Qasa) (exported or on-site manufactured) for the main entrance, double-faced of plate thickness 1.50mm including glass pans, door frame 13.5*4.5cm 2.5mm thickness, Film Coated Residential Steel Entrance Door Glassy Finished Style, including special switch, gate lock, door stopper, rubber, polycarbonate filled, special guard bar, thermal paint & metal frames 6*22cm, Mercury glass 15x40cm with 3 cm Styrofoam polystyrene inside the door, Central lock system, with additional horizontal a lock with three concealed hinges with all necessary works, samples required for final approval.

The actual quantity is 5.5 m2.

Annex C LOT1- Financial Offer Form: Metal Door (Qasa): Provide and install decorative metal doors (Qasa) (exported or on-site manufactured) for the main entrance, double-faced of plate thickness 1.50mm including glass pans, door frame 13.5*4.5cm 2.5mm thickness, Film Coated Residential Steel Entrance Door Glassy Finished Style, including special switch, gate lock, door stopper, rubber, polycarbonate filled, special guard bar, thermal paint & metal frames 6*22cm, Mercury glass 15x40cm with 3 cm Styrofoam polystyrene inside the door, Central lock system, with additional horizontal a lock with three concealed hinges with all necessary works, samples required for final approval.

The actual quantity is 5.5 m2.

Annex C LOT2- Financial Offer Form: The Supply material and do earthing protection system for the electrical network by using three copper rods 1m inside three ground holes and connecting the rod with the mainboard by cable 1 X 70mm² and distributed to (FDB) by 1 X 25mm² finally by 1 X 2.5mm² for sockets, filling the hole with special salt and coal. The price includes the construction of manhole 40*40cm with HDPE or aheen cover. The formula has been set up to capture the sub-total of the line.

Extension of the Closing Date: Closing date 3rd October 2024 at 12:00 hrs. Iraq standard time is extended to 7th October 2024 at 12:00 hrs. Iraq standard time. The deadline for submitting offers has been extended due to amendment made to some of the cells as mentioned above in the BOQ and the financial offer form for Lots 1 & 2 respectively.

All other terms and conditions remain unchanged.

Giorgia Anesin
Senior Supply Officer
UNHCR Iraq Operation