

**ANNEX B: TECHNICAL SPECIFICATION/BOQ
RFQ NO.2024/SOP/SCU/009**

UNHCR SUB OFFICE PESHAWAR

RENOVATION WORKS AT VRC AZAKHEL NOWSHERA

BILL OF QUANTITIES

S.No.	ACTIVITIES DESCRIPTION	Qty	Unit
1	Metallic paint works of existing benches in the facility, of approved color	230	No.
2	Repair of existing benches including repair/replacement of wooden planks and nails etc.	70	No.
3	Painting Distemper (2 coat) of family segregation hall, 2 halls, of approved color	4600	sqft
4	Painting of main entrance gates, both sides of VRC and PCM, of approved color	960	sqft
5	Paint works of external red brick wall	1500	sqft
6	Paint works of external shed pillers and frame in white color	1100	sqft
7	Paint works of BHU containers no. 19,20, 26, of approved color	1350	sqft
8	Paint works of containers no. 1,4,17,26, of approved color	1800	sqft
9	Painting of refugees' entry gate and fence	950	sqft
10	Paint works of 3 backup generators	960	sqft
11	Plain Cement Concrete (3") flooring in refugee screening area, 1;2:4, with proper compaction	950	cuft.
12	Extension of screening shed, including additional pillars and other fixtures	510	sqft
13	Painting of shed frame of screening area including the extension area (item. 11) in white color	4300	sqft
14	Cleaning, Dressing, Leveling & Compaction of existing surface, 3" thick PCC (1:4:8) & 2" thick Tuff Tiles installation in red and yellow color, over 2" thick sand, Complete in all respects	3550	sqft
15	Repair of entrance gate between PCM and VRC	1	Job
16	Painting of sign boards-Main GT road, VRC entrance and inside VRC	1	Job
17	Repair of female and male search cabins, (7'x7'x8') each	2	No.

Company Name:

Contact Details:

Signature / Stamp: