

	Removing existing graffiti from the surface of walls and Preparing the walls for new water mat colour. Providing and applying prime coat including the finishing coats of water mat on roof and walls with sequence of (primer 1 coat, wall putty, primer 1 coat ,final finishing materials 2 coats) as specified. Ground Floor: Male Hall with washroom roof . Female hall with washroom roof. Entrance corridor ,connecting lobby,Porch First Floor: staircase area , Lounge Hall Connecting Lobby to Terrace Terrace Walls Make: (ICI/Nippon Paint)						SQFT	6325		
14	PVC wall cladding sheets									
	providing and applying of 3mm pvc wall sheets (10"x9'-6") in male & female halls (4' up from floor till roof) in all respect. Make: roval or equivalent						SQFT	1220		
15	SPC Flooring									
	Providing and Applying of 4mm spc flooring sheet tiles in connecting lobby of G.F in all respect. Providing & fixing of approved shade & texture of reducers for PVC 4mm spc flooring having length of 8 feet lin all respects.	SPC & Reducers					SQFT	165		
		Reducers					NOS	9		
16	Exhaust fans									
	Providing & installing of exhaust fan 9" dia for ground floor halls washrooms in all respects. Make: voldam or equivalent	2					NOS	2		
17	Wallpaper									
	Providing and applying of korean wallpaper on existing marble claddings on staircase walls Including all items and charges to complete the work as per specification.		22'	20'			SQFT	440		
18	Wall Cabinets									
	Provide and fixing of lasani sheets for cabinet sub structure with 18mm thick lasani sheets as finishing of cabinets, Including all items Brass approved (handles, locks and hardware) Complete in all respect as per instruction. Make: (Al-Noor Lasani/ZRK Lasani)		17'		8'		SQFT	136		
19	Providing and installing of Neolux – Black Linear Hanging Light 36W in entrance corridor with wire points in all respect.						NOS	6		
GRAND TOTAL PKR										
	Name of Company									
	Contact Person									
	Signature									
	Stamp Date									